

**BID ADDENDUM ONE**  
**BID DOCUMENTS & SPECIFICATIONS**  
**FOR:**  
**BARTON AVENUE (FAIRMONT PARK) LEVEE EXTENSION PROJECT**

Quantities for Itemized Bid have been revised and are attached. Please use revised Bid Sheet.

# ITEMIZED PROPOSAL

Note: All Unit Prices and Totals Must Be Written or Typed in Black Ink

CDBG-DR

BARTON AVENUE (FAIRMONT PARK) LEVEE EXTENSION

BID DESCRIPTION	QTY	UNITS	UNIT PRICE	TOTAL
CLEARING & GRUBBING	1	LS		
STRIP & STOCKPILE TOPSOIL	4670	SY		
UNCLASSIFIED EXCAVATION & DISPOSAL	2135	CY		
EMBANKMENT IN-PLACE (ENGINEERED FILL)	5500	CY		
6" DIA. PERFORATED TOE DRAIN	585	LF		
TOE DRAIN STONE FILTER-COURSE	135	CY		
TOE DRAIN STONE FILTER-FINE	430	CY		
GEOTEXTILE FABRIC	5705	SY		
TOPSOIL, SEED & MULCH	3800	SY		
ASPHALT BINDER COURSE	145	TONS		
ASPHALT TOP COURSE	20	TONS		
MOBILIZATION & DEMOBILIZATION	1	LS		
EROSION & SEDIMENTATION CONTROL ALLOWANCE	1	LS		
SURVEY & STAKEOUT ALLOWANCE	1	LS		
TEMPORARY MPT (DETOURS, SIGNAGE & BARRICADES)	1	LS		
MATERIAL TESTING (FIELD & LAB)	1	LS		
<b>GRAND TOTAL:</b>				